

15-847
00086-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County. Sec. 28 Twp. 26S Rge. 16 (X) (W)

Location as "NE/CNW*SW*" or footage from lines C W/2 NW/4

Lease Owner Aurora Gasoline Company

Lease Name Simpson Well No. 1

Office Address 802 Union National Building - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-18 19 56

Application for plugging filed 9-18 19 56

Application for plugging approved 9-18 19 56


Plugging commenced 9-18 19 56

Plugging completed 9-18 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4572 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	No Show	3836		8 5/8	403'	
Toronto		3854				
Douglas		3871				
Brown Lime		3889				
Lansing		4004				
Base Kansas City		4335				
Cherokee Shale		4440				
Mississippi		4477				
Viola		4548				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to 300' - Plug set and cemented with 20 sacks, hole filled with mud and hulls. Top plug set at 35' and cemented with 10 sacks cement. Hole plugged.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Johnie S. Carter Drilling Company

Address 406 C. A. Johnson Building - Denver, Colorado

STATE OF Kansas, COUNTY OF Butler, ss.
Joe W. Cain of L. C. Smitherman Drlg. Co. (employed by operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. L. C. SMITHERMAN, DRILLING CO.

(Signature) Joe W. Cain
For Johnie S. Carter Drilling Company
406 C. A. Johnson Building - Denver, Colorado
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 56

Notary Public

My commission expires October 23, 1958.

PLUGGING
FILE SEC 28 T. 26 R. 16W
BOOK PAGE 101 LINE 5

15.047-00086-0000

#1 SIMPSON

Company: Aurora Gasoline Co.
Contractor: Johnie S. Carter
Commenced: September 2, 1956
Completed: September 18, 1956
T.D. 4572'
Init. Prod. D & A

Location: C W/2 NW/4 Sec. 28-26S-16W
EDWARDS COUNTY, KANSAS
Elevation:
Casing: 8-5/8" - 400' cemented
w. 275 sacks-

Figures Indicate Bottoms of Formations:

Depth	Formation:
0 - 130	Clay and Sand
130 - 315	Sand
315 - 330	Shale and Sand
330 - 370	Sand and Blue Shale
370 - 400	Blue Shale and Red Bed
400 - 975	Sand and Red Beds
975 - 1130	Sand and Shale
1130 - 1245	Sand
1245 - 1465	Sand and Shale
1465 - 2915	Shale and Lime
2915 - 3050	Shale
3050 - 3335	Shale and Lime
3335 - 3440	Lime w/ shale breaks
3440 - 3630	Shale and Lime
3630 - 3710	Lime
3710 - 3990	Shale and Lime
3990 - 4365	Lime
4365 - 4460	Lime and Shale
4460 - 4495	Lime and Sand
4495 - 4534	Cherty Lime
4534 - 4562	Miss. Cherty Lime
4562 - 4572	Chert and Shale
4572	R. T. D.

We hereby certify the above and foregoing to be a true and correct copy of the Log on the #1 Simpson, located in the Center of the West Half of the Northwest Quarter of Section 28, Township 26 South, Range 16 West, Edwards County, Kansas.

JOHNIE S. CARTER DRILLING COMPANY



Subscribed and sworn to before me this 20th day of September 1956.


Notary Public

My commission expires August 10, 1959.

PLUGGING
FILE SEC 28 T 26 R 16W
BOOK PAGE 101 LINE 5