

15-047-06069-00-01


Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

EDWARDS County. Sec. 24 Twp. 26S Rge. 16 (E)W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name JOHNSON Well No. 1
Office Address BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) GAS WELL
Date well completed JUNE 1 19 56
Application for plugging filed OCTOBER 11 19 66
Application for plugging approved OCTOBER 13 19 66
Plugging commenced OCTOBER 12 19 66
Plugging completed JANUARY 11 19 67
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production UNKNOWN 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4546 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	329	NONE
				5 1/2	4546	3292

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4546 - 4375 - SAND
 4375 - 4340 - 5 SACKS CEMENT
 4340 - 325 - MUD
 325 - 315 - ROCK BRIDGE
 315 - 309 - 1 SACK CAL SEAL, 1 SACK CEMENT
 309 - 237 - 24 SACKS CEMENT
 237 - 40 - MUD
 40 - 30 - ROCK BRIDGE
 30 - BASE - 10 SACKS CEMENT

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 16 1967
 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss. T.L. NUTT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.L. Nutt
BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of JANUARY 19 67

My commission expires JULY 31, 1970
Mary M. Swanson
Notary Public.