

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-047-20,565-0000

LEASE NAME Walls Bros.

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line  
 SW NW SW

SEC. 28 TWP. 26S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 7-2-87

Plugging Completed 7-7-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR L.D. Drilling, Inc.

Rt. 1 Box 183B

ADDRESS Great Bend, Kansas 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify?          Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom T.D. 4612'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 365'   | none       |
|           |         |      |    | 5-1/2" | 4600'  | 2346'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 4430' and 5 sacks cement. Shot pipe @2809', 2630', 2386', pulled a total of 58 joints of 5-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel.  
Plugging Complete.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050'

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1987

*Gene L. Hoover*  
 Notary Public

My Commission Expires:         



JUL 15 1987