


15-047-20160-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County, Sec. 32 Twp. 26 Rge. 16 (E) W (W)
SE SE NE
Location as "NE/CNW/SW" or footage from lines
Lease Owner J. Mark Richardson
Lease Name Young Well No. 1
Office Address 200 O.W. Garvey Bldg. Wichita, Kan.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 2-1 19 75
Application for plugging filed Aug. 20 19 75
Application for plugging approved Aug 23 19 75
Plugging commenced Aug 24 19 75
Plugging completed Aug 28 19 75
Reason for abandonment of well or producing formation Low fluid

If a producing well is abandoned, date of last production July 19 75
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G Russell Biberstein
Producing formation Kinderhook Depth to top 4506 Bottom 4527 Total Depth of Well 4580
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi-Kinderhook				4 1/2	4579	2280
				8 5/8	474	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 40 sacks cement plug to 3373 feet. Filled hole with mud. (Allied Cement CO.)
Shot casing 2275 feet. Pulled 2280 ft. Built rock bridge at 240 ft;
Fill hole with 4 yards cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cement Co.
Address Kiowa, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
J. Mark Richardson (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the well as filed and that the same are true and correct. So help me God.

(Signature) J. Mark Richardson
J. Mark Richardson, 200 O.W. Garvey Bldg.
Wichita, Kan. 67202 (Address)

SWORN TO before me this 10 day of Oct. 19 75

March 8, 1977

Ellen Fagen Notary Public.



NOV 10 1975
COMM. EXPIRES 3/8/77

15-047-20160-0006

Gabbert-Jones, Inc.
WICHITA, KANSAS
DRILLERS' WELL LOG

Young #1
100' SE of SE-SE-NE Sec 32-26-17W
Edwards County Kansas

Commenced: 11-12-74

Completed: 11-26-74

OPERATOR: J. MARK RICHARDSON

Depth From	to	Formation	Remarks
0	377	Sand	Ran 10 jts of used 28# 8 5/8" csg set @ 414' Cemented
377	418	Shale-Redbed	w/350 sks Cement Common
418	656	Shale	2% Gal-3% CC PD @ 5:00 a.m.
656	1300	Shale-Shells	11-13-74 Cement Circ
1300	1590	Redbed-Shale	
1590	2235	Shale-Redbed	
2235	4020	Lime-Shale	
4020	4580	Lime	
	4580 TD		Ran 142 jts New 10 1/2" 4 1/2" csg set @ 4579' Cemented w/125 sks Common PD @ 2:50 A. M. 11-26-74

I, James S. Sutton II, certify this is a correct copy of the Drillers Log for the well drilled 100' SE of SE-SE-NE Sec 32-26-16W Edwards County, Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6th day of December, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC



My Commission Expires: November 29th, 1975

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1975

CONSERVATION DIVISION
Wichita, Kansas