


WELL PLUGGING RECORD

Give All Information Completely  
\*As Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Edwards County, Sec. 33 Twp. 26 Rge. 16 ~~XXX~~ (W)

Location as "NE/CNW&SW&" or footage from lines SW NW NE  
Lease Owner Clark Knight Drilling Company, Inc.  
Lease Name Ed Giles Well No. 1  
Office Address P. O. Box 162 - Great Bend  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-18 19 57  
Plugging completed 10-18 19 57  
Reason for abandonment of well or producing formation Non-commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4572 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite	1097'					
	1104' of Surface pipe set and cemented w/500 sack and circulated.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well was D and A  
Filled hole with heavy mud  
Set plug @ 300' and dumped 30 sks cement.  
Filled hole with heavy mud up to 35'  
and set plug and dumped 10 sks cement.

STATE CORPORATION COMMISSION  
OCT 21 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
L. C. Knight (~~employee or owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Knight  
P. O. Box 162 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of October, 19 57

My commission expires April 1, 1959  
Ulanda Nichols Notary Public.

PLUGGING  
FILE SEC 33T 26 R 160  
BOOK PAGE 55 LINE 36

15-047-10094-0000

Company: Clark Knight Drilling Co., Inc.  
Farm: Ed Giles No. 1

Sec. 33-26-16W  
SW NW NE

Total Depth: 4572'  
Comm. 9-26-57 Comp. 10-17-57  
Shot or Treated:

County: Edwards

Contractor: Ari-Kan Drilling Company  
Issued:

Elev. 2099 DF  
2096 GR

Casing 8 5/8" 1104'

Figures indicate bottom of formations:

- 40 Sand Clay
- 290 Sand and Shale
- 320 Red Bed and Sand
- 420 Shale and Shells
- 485 Sand
- 715 Shale and Red Bed
- 785 Shale and Shells
- 1096 Sandy Gravel
- 1135 Anhydrite
- 1430 Red Bed and Shale
- 2160 Shale and Shells
- 2590 Lime
- 2605 Shale and Shells
- 3075 Lime and Shale
- 3103 Shale
- 3320 Shale and Lime
- 3380 Shale and Shells
- 3825 Lime and shale
- 3861 Lime
- 4025 Shale and Lime
- 4408 Lime
- 4495 Lime and Shale
- 4517 Sand and Cherty Lime
- 4572 Chert and Shale

4572' T. D.

RECEIVED  
STATE OF KANSAS

OCT 30 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 33-26-16W  
BOOK PAGE 55 LINE 36