

15-247-20671-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 33 Twp. 26S Rge. 16W-E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C-SW SW NE

Lease Owner Eagle Petroleum Corporation
Lease Name Giles Well No. 1
Office Address 104 S. Broadway, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed April 26, 19 80
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced April 26, 19 80
Plugging completed April 26, 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4,618'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	420'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,618 ft. (rotary total depth) to 600 ft. Set plug at 600 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 360 ft. Set plug at 360 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil well cementing pump truck through 4 1/2 inch drill pipe.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Employee of owner or owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 30th day of April, 1980

Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

15-047-20671-0000

COMPANY Eagle Petroleum Corporation

SEC. 33 T. 26S R. 16W

FARM Giles NO. 1

LOC. C-SW SW NE

COUNTY Edwards

ROTARY TOTAL DEPTH 4,618'
COMM. April 17, 1980 COMP. April 26, 1980
CONTRACTOR H-30, INC. (Rig #7)
ISSUED April 30, 1980

CASING

10 3/4"
8 5/8" Set at 420' cemented w/325 sxs cement
5 1/2"
4 1/2"

ELEVATION 2,088' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	423'
Sand, Shale and Shells	1,195'
Shale and Lime	2,055'
Lime and Shale	2,117'
Shale and Lime	2,292'
Lime and Shale	2,824'
Shale and Lime	3,075'
Lime and Shale	4,618'
Rotary Total Depth	4,618'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

STATE RECEIVED
CONSERVATION COMMISSION
MAY - 2 1980
CONSERVATION DIVISION

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 30th day of April, 1980.

NOTARY PUBLIC
EDWARDS COUNTY, KANSAS

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982