

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-21-994-0000 ²⁰⁹⁷⁴

LEASE NAME Cudney B

WELL NUMBER 9

1815 Ft. from S/N Line of Section (circle one)

990 Ft. from E/W Line of Section (circle one)

SPOT LOCATION Irregular-Section

SEC. 4 TWP. 26 S. RGE 16 (E) or (W)

COUNTY Edwards

Date Well Completed _____

Date Plugging Commenced 4-17-95

Date Plugging Completed 5-2-95

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

LEASE OPERATOR FG Holl Co. LLC

ADDRESS 6427 E. Kellogg Box 780167

CITY, STATE, ZIP Wichita, Ks. 67228-0167

PHONE#(316)684-8481 OPERATORS LICENSE NO. 5056

Charater of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-1-95 (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation(s) _____ Depth to Top _____ Bottom _____ T.D. 4535

Show depth and thickness of all water, oil and gas formations. PBTD: 4498

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	433	8 5/8	433	0
		0	4530	4 1/2	4530	3093 ft.

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

3 hulls- 10 gel- 50 sx. cement- 10 gel- 1 hulls- 8 5/8 plug- 150 sx. cement on top. 60-40 poz 6% gel.

Redi-mix to surface.

Well was sanded to 50' above top perfs + 4 sx. cement on top of sand.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address PO Box 847 Pratt, Ks.

NAME OF PARTY, RESPONSIBLE FOR PLUGGING FEES: FG Holl Co. LLC

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of operator or (operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Judy Berry

(Address) PO PWS, Inc.

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1995

Dorothy M. Ferguson
 Notary Public

My Commission Expires: 02/06/97



STATE CORPORATION COMMISSION
 MAY 20 1995
 CONSERVATION DIVISION
 WICHITA, KANSAS