

15-155-21016-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-21,016

LEASE NAME Locke

WELL NUMBER 1

SPOT LOCATION SE SE SE

SEC. 33 TWP. 24 RGE. 8 ~~XXX~~ or (W)

COUNTY Reno

Date Well Completed 9-23-84

Plugging Commenced 9-23-84

Plugging Completed 9-23-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mallonee-Warren, Ltd.

ADDRESS 302 N. Rock road, Suite 206 Wichita, KS 67206

PHONE # (316) 687-5115 OPERATORS LICENSE NO. 9092

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Merlan Unruh  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 272' w/40 sacks 50/50 pozmix 4% gel 2% cc. thru drill pipe

Top Plug: @ 60' w/35 " " " " " " " "

10 sacks cement in Rat Hole  
5 sacks cement in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (employee of operator) or

~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, KS 67202

9-26-84  
SFP 26 1984

(Signature) Ervin Neighbors

(Address) Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 24 day of Sept, 1984

Alvin M. Hague  
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: September 18, 1984  
DATE COMPLETED: September 23, 1984

Mallonee-Warren, Ltd.  
LOCKE #1  
SE SE SE  
Sec. 33, T24S, RSW  
Reno County, Ks.

ELEVATION:

0 - 1190' Surface Soil, Sand, Red Bed  
1190 - 2978' Shale & Lime  
2978 - 2982' Shale  
2982 - 3181' Lime & Shale  
3181 - 3556' Lime  
3556 - 3673' Shale & Sand  
3673 - 3700' Chert & Lime  
3700' RTD

FORMATION DATA

Heebner 2978'  
Lansing 3181'  
Base K.C. 3556'  
Cherokee Sh. 3659'  
Mississippi 3673'  
RTD 3700'

Surface Pipe: Set new  
8-5/8", 20# pipe @ 222'  
w/165 sacks 60/40 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
County of Barton) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 24 day of September 1984.

My Comm. Expires:

4-29-86

*Lorilyn M. Idagie*  
Notary Public

COMMISSION

SEP 26 1984

9-26-84