


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 6 Twp. 24S Rge. (X) 9 (W)
Location as "NE/CNW&SWK" or footage from lines C SW NE
Lease Owner John C. Graves, et al
Lease Name Moeckel Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 21, 1968
Application for plugging filed May 21, 1968
Application for plugging approved May 21, 1968
Plugging commenced May 21, 1968
Plugging completed May 21, 1968
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3786 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 215 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas

6-7-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1968

My commission expires May 9, 1971

Betty Brandt

Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves, et al DRILLING COMMENCED: May 14, 1968
 505 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: May 21, 1968
 505 Union Center
 Wichita, Kansas

CASING RECORD: 10 Jts. 225' 8-5/8" LOCATION: Moeckel No. 1
 cemented with 200 sacks C SW NE
 Section 6-24S-9W
 Reno County, Kansas

0 - 110	Surface, soil & sand
110 - 227	Red bed
227 - 1045	Red bed, shale & shells
1045 - 1390	Shale & shells
1390 - 1685	Lime & sandy shale
1685 - 1910	Sandy lime
1910 - 2525	Lime & shale
2525 - 2845	Lime & shale with chalk streaks
2845 - 3117	Lime
3117 - 3122	Shale
3122 - 3140	Lime
3140 - 3260	Shale
3260 - 3287	Shale & sandy shale
3287 - 3650	Lime
3650 - 3737	Shale & lime
3737 - 3786	Chert

3786 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John C. Graves*
 President

STATE OF KANSAS)
) ss:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 24th of May, 1968.

Betty Brandt
 Betty Brandt Notary Public

My commission expires May 9, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 7 1968
 CONSERVATION DIVISION
 Wichita, Kansas

6-7-68