

WELL PLUGGING RECORD

Reno

County. Sec. 30 Twp. 24S Rge. 7W (~~XX~~) (~~XX~~)X

Location as "NE/CNW%SW%" or footage from lines. SE SE SW

Lease Owner Hershberger Enterprises, Inc.

Lease Name O'Hara Well No. 1
Office Address Suite 230, O.W. Garvey Bldg., Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 27, 19 73

Application for plugging filed Verbal Application 19

Application for plugging approved Verbal Approval 19

Plugging commenced August 27, 19 73

Plugging completed August 27, 19 73

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____ Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2,078 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 2,078 feet

(rotary total depth) to 400 feet. Set plug at 400 feet and cemented

with 40 sacks cement. Filled hole with heavy rotary mud from 400

feet to 200 feet. Set plug at 200 feet and cemented with 25 sacks

cement. Filled hole with heavy rotary mud from 200 feet to 40 feet.

Set solid plug at 40 feet and cemented to cellar with 10 sacks cement.

2 sacks cement in rathole.

Plugging operations accomplished utilizing Halliburton

Oil Well Cementing pump truck through $4\frac{1}{2}$ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.

Address 200 North Main, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dean R. Blitting, Agent

(Employee of owner) ~~OK~~ (Owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature)

200 North Main, Wichita, Kansas 67202

(Address)

Subscribed and sworn to before me this 30th day of August, 1973

My commission expires June 30, 1974

Elsie Willison

Notary Public

15-155-20225-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Hershberger Enterprises, Inc.
FARM O'Hara NO. 1


SEC. 30 T. 24S R. 7W
LOC. SE SE SW

TOTAL DEPTH 2,078'
COMM. August 23, 1973
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COMP. August 27, 1973

COUNTY Reno

KANSAS



CASING

20	10
15	8-5/8" 206' cemented w/200 sxs cement ELEVATION
12	6
13	5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	210'
Shale	760'
Shale and Lime	1,431'
Lime and Shale	2,078'
Rotary Total Depth	2,078'

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1973
CONSERVATION DIVISION
Wichita, Kansas
9-4-73


I hereby certify the above and foregoing
to be a true and correct log of the above
described well as shown by the drilling
reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary
Public in and for said county and state this
30th. day of August, 1973.



Elsie Willison
Elsie Willison - Notary Public