

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Form CP-4

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Reno County, Sec. 9 Twp. 24 Rge. 8 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines NE/4 SW/4 NW/4
Lease Owner Twyllah O. Gaskill
Lease Name Deck Well No. 1
Office Address 633 Beacon Bldg. Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 26 19 65
Application for plugging filed May 26 19 65
Application for plugging approved May 26 19 65
Plugging commenced May 26 19 65
Plugging completed May 26 19 65
Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3, 766 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS					CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	259 1/2'	Cmtd w/200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill w/ heavy mud to 250'
Set bridge plug @ 250' w/ 1/4 sax hulls on plug
Dump 25 sax cement on plug thru 4 1/2" drill pipe
Fill w/ heavy mud to 40'
Set bridge plug @ 40' w/ 1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1965
6-23-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
Shields Bldg. Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 65
[Signature]
Notary Public.
My commission expires Sept. 27, 1967



Shields


15-155-30020-0000

Russell, Kansas

WELL LOG

Operator: Twyllah O. Gaskill
Well: Deck #1
Commenced: May 17, 1965
Completed: May 26, 1965
Contractor: Shields Drilling Co., Inc.

Well Description: NE SW NW
Sec. 9-24S-8W
Reno Co., Kansas



CASING RECORD
Size Run Pulled
8 5/8" 259 1/2' Cmtd w/ 200 sax

Elevation:

Treatment:

Production:

Tops:

..... Figures Indicate Bottom of Formations

Surface soil & sand	45'
Sand & redbed	250'
Anhydrite	275'
Shale, shells, redbed & salt	710'
Shale & lime	1,260'
Lime	1,775'
Lime & shale	2,686'
Lime	3,045'
Shale & lime	3,220'
Lime	3,660'
Lime & chert	3,766' RTD

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1965
6-23-65
CONSERVATION DIVISION
Wichita, Kansas

Notes