

STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno

County, Sec. 20 Twp. 24 Rge. 7 (E) (W)

Location as "NE/CNW*SW*" or footage from lines SE SE NE

Lease Owner WHITCRAFT & STURGES

Lease Name A. L. Miller Well No. 1

Office Address 512 Orpheum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed April 20 19 62

Application for plugging filed July 3 (?), 19 62

Application for plugging approved JULY 6, 19 62

Plugging commenced July 6 19 62

Plugging completed July 12 19 62

Reason for abandonment of well or producing formation Made 150 BHPD and 2 BOPD

If a producing well is abandoned, date of last production May 20, 19 62

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Herm Justice

Name of Conservation Agent who supervised plugging of this well

Producing formation Lansing-Kansas City Depth to top 3492 Bottom 3495 ? Total Depth of Well 3495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	105'	8 5/8"	yes	1no
		0	3492	4 1/2"	yes	3083'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand and gravel. Dumped 5 sacks of cement in bottom. Shot pipe off at 3083'. Pulled pipe and mudded hole to 250'. Set rock bridge and dumped 20 sacks of cement. Finished mudding hole to 30'. Set rock bridge and dumped 10 sacks of cement in base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1962

CONSERVATION DIVISION
Wichita, Kansas

9-4-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address RR 4, Hutchinson, Kansas

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July 19 62

My commission expires October 18, 1965

Notary Public.

