

DEC 5 1988

To: 1 040201
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,649-0000

C SE/4, SEC. 35, T 25 S, R 16 W/X

1320 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Cudney Well # B-2

Operator: Oil Producers Inc. of Kansas

County Edwards 143.88

Name & Address Box 8647

Well Total Depth 4427 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 446

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:45 a.m. Day: 5 Month: 12 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4418' Open hole 4418-4427'

1st plug sand back to 4360' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2475' of 4 1/2" casing (if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1988
12-13-88

CONSERVATION DIVISION
Wichita, Kansas

INVOICE observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 12-13-88

INV. NO. 23340 12-5 FEB 10 1989