

10139

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-19002-0060
C SW NE SEC. 35, T 25 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 3400 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 760 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CUDNEY WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS 145.28

OPERATOR LICENSE # 31938 7/7

WELL TOTAL DEPTH 4470 FEET

OPERATOR: RAMA OPERATING CO. INC. PRODUCTION CSG: SIZE 4.5 @ 4468' WITH 125 SX

NAME AND P.O. BOX 159 SURFACE CASING: SIZE 8 1/2" @ 351' WITH 350 SX

ADDRESS STAFFORD, KANSAS 67578

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL E-26994 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 05 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM SMITH

RECEIVED STATE CORPORATION COMMISSION

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

III 14 2000
7-14-00

WERE: PERFS AT 4366-4380 RECOVERED 2500' OF 4.5" CASING

CONSERVATION DIVISION
Wichita, Kansas

SAND TO 4250' WITH 4 SX CEMENT ON TOP. LOAD HOLE WITH MUD: 1ST PLUG @ 1050' W/ 50 SX. CMT. THRU CASING 2ND. PLUG @ 380' W/ 50 SX. CMT 3RD. PLUG @ 40 TO SURFACE w/ 10 SX. CMT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 07 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND TO 4250' WITH 4 SX CEMENT ON TOP. ALLIED PUMPED 1ST. PLUG @ 1050' THRU 4.5" CASING W/ 50

SX. CEMENT 2ND. PLUG @ 380' W/ 50 SX. CEMENT 3RD. PLUG @ 40 TO SURFACE W/ 10 SX. CEMENT

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500 OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING INVOICED SIGNED

[Signature] (TECHNICIAN)

DATE 7/18/00
WELL NO. 1060087

FORM CP-2/3

[Circular Stamp]