

15-047-21265-00-00

1 080578

DEC 12 1986 15-047-21265-0000

API NUMBER ~~15-047-20,747~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SE, SEC. 35, T 25 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line

990 feet from E section line

Operator License # 8061

Lease Name Cudney Well # 3

Operator: Oil Producers Inc. of Kansas

County Edwards 145.44

Name & Address Box 8647

Well Total Depth 4475 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:15 a.m. Day: 12 Month: 12 Year: 1986

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4474' PBSD 4465' Perfs at 4408-28', 4390-98', 4354-64' Elevation 2063' GL

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 2 sx hulls, and 150 ALT cement.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 12 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 2 sx hulls, released 8 5/8" wiper plug and pumped 150 sx ALC cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used ALC cement by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

STATE CORPORATION COMMISSION
DEC 17 1986
12-17-86
CONSERVATION DIVISION
Wichita, Kansas

DATE 12-17-86

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 15658