

8-2-88 15-047-00365-00-00

To: 1 120119  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 8/14/58

NE NE SE, SEC. 36, T 25 S, R 16 W/EX  
2310 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622

Operator: Jason Oil Company  
Name & Address: P.O. Box 701  
Russell, KS 67665

Lease Name Lane Well # 1

County Edwards 144.30

Well Total Depth 4440 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 396

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 2 Month: 8 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4438' Perfs at 3889-4376' (7 sets)

1st plug sand back to 3840' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-4-88  
AUG - 4 1988

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed at Kansas Hour: 12:30 p.m. Day: 2 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3840' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 0-600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2400' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOLVED

observe this plugging.

DATE 8-11-88

Signed Duane Rankin (TECHNICIAN)

INV. NO. 21838