

1 120430

6-615-047-00390-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/9/61

C SW NW, SEC. 36, T 25 S, R 16 W/E

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Cudney Well # 1C

Operator: National Cooperative Refinery Assoc.

County Edwards 143.49

Name & Address 6000 West 10th

Well Total Depth 4415 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 6 Month: 6 Year: 1990

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 4414' PBSD 4389' Perfs at 4366'

1st plug sand back to 4316' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 6 Month: 6 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4316' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by B.J. Services. Recovered 2310' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (if desired, please observe this plugging.)

DATE 6-25-90

Signed Duane Rankin (TECHNICIAN)

INV. NO. 28461

1990 6-13-90