

1 120429

6-6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,808-00-00

SW SW SW, SEC. 36, T 25 S, R 16 W/E
330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Cudney Well # 3 CL

Operator: National Cooperative Refinery Assoc.
Name & Address: 6000 W. 10th
Great Bend, KS 67530

County Edwards 144.95
Well Total Depth 4460 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 6 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 4459' PBD 4437' Perfs at 4410-20'

1st plug sand 5 1/2" casing back to 4360' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 6 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4360' and dumped 5 sx cement
on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Welded plate on 8 5/8".

Pumping pressure 0-300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by B.J. Services. Recovered 2215' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-90

INV. NO. 28462

observe this plugging.
JUN 13 1990
6-13-90
DIVISION
CONCRETE

Signed Duane Rankin
(TECHNICIAN)