

6-6 15-047-00077-00-00

To: 1 120431
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 10/10/58

NE NE SW, SEC. 36, T 25 S, R 16 W/E
2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5565

Lease Name Cudney Well # 1 CL

Operator: National Cooperative Refinery Assoc. County Edwards
Name & Address 6000 W. 10th.
Great Bend, KS 67530

146.02
Well Total Depth 4493 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 6 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 4492' PBTD 4455' Perfs at 4350-60'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 6 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-350 psi and shut in 125 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by B.J. Services. Recovered 2047' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 6-25-90

INV. NO. 28460

JUN 23 1990
6-13-90

Signed Duane Rankin
(TECHNICIAN)