

1 060938

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl
Name & Address 6427 East Kellogg
Wichita, KS 67207

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 3 Month: 3 Year: 19 87

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4563' PBTD 4522' Perfs at 4427-31, 4417-21'

1st plug CIBP at 4400' with 2 sx cement, 3^{2nd plug} sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,
1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 3 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIBP at 4400' with 2 sx cement,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 130 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form)

INVOICED
(if additional description is necessary, use BACK of this form) observe this plugging.

DATE 3-9-87

INV. NO. 16313

MAR 3 1987
API NUMBER 15-047-20,700-00-00
SW SW NW, SEC. 2, T 25 S, R 17 W/E
3080 feet from S section line
4880 feet from E section line
Lease Name Hawley "C" Well # 2-2
County Edwards 148.36
Well Total Depth 4565 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Signed Paul A. Luthi
(TECHNICIAN)
STATE CORPORATION COMMISSION
3-5-87
MAR 19 1987
CONSERVATION DIVISION
Wichita, Kansas