

1 060963

15-047-00207-00-01

MAY 2 1 1987

API NUMBER 15-Drill completion 2/7/63

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NW, SEC. 9, T 25 S, R 17 W/EX

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Britton Well # 1

Operator: Texas Energies, Inc.

County Edwards 158.41

Name & Address

P.O. Box 947

Well Total Depth 4874 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 21 Month: 5 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4775' Perfs at 4477-4678'

1st plug sand back to 4420' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 5:15 p.m. Day: 21 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sand back to 4420' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 250 psi.

Remarks: Recovered 1992' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 5-27-87

INV. NO. 17006

Signed Paul A. Luthi

(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
5-26-87MAY 26 1987
CONSERVATION DIVISION
Wichita, Kansas