

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- 047- 20,838-00-00
 NW NW NE , Sec. 11 , T 25 S, R 17 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Tubbs-Burr Well # 1-11

Operator: F. G. Holl
 Name & 6427 East Kellogg
 Address Wichita, KS 67207

County Edwards

Well Total Depth 4565 feet 148.36

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 14 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4559 Perfs 4436-40 PBTB 4485

1st plug pumped 35 sx cement and stopped at 4380'

2nd plug squeezed through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 0

Signed J. M. [Signature]
 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 14 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4559 Perfs 4436-40 PBTB 4485

1st plug pumped 35 sx cement and stopped at 4380'

2nd plug squeezed through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 100 sx cement.

Maximum pressure 500# and shut-in pressure 0.

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Allied.

They recovered 2483' of 4 1/2" production casing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
 DATE 3-5-84
 INV. NO. 0516

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 29 1984
2-29-84
 CONSERVATION DIVISION
 Wichita, Kansas

Signed J. M. [Signature] ✓
 (TECHNICIAN)