

3-24-88

1 061084

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,812-00-00

NE NE NW, SEC. 14, T. 25 S, R. 17 W EX

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Schartz Well # 1-14

Operator: F.G. Holl Company

County Edwards

Name & Address

6427 East Kellogg

Well Total Depth 4595 feet

P.O. Box 780167

Conductor Pipe: Size _____ feet

Wichita, KS 67207

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:10 p.m. Day: 24 Month: 3 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4593' PBD 4505' Perfs at 4451-55'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:10 p.m. Day: 24 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2325' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-29-88

INV. NO. 20240

Signed Paul A. Luthi (TECHNICIAN)

STATE RELEASED
CORPORATION COMMISSION

MAR 29 1988
3-28-88
CONSERVATION DIVISION
Wichita, Kansas