

1030222

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,164-60-00

NW SE NW, SEC. 15; T. 25 S, R. 17 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ foot from W/E section line

Operator: F. G. Holl

Lease Name Wheaton Well # 1-15

Name & Address 6427 East Kellogg

County Edwards

Well Total Depth 4670 feet

P. O. Box 18167

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, KS 67218

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 9 Month: July Year: 19 84

Plugging proposal received from Neal Pedicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4669' - PBD 4560' Perfs 4516 - 40'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Allen W. ...  
(TECHNICIAN)

Plugging Operations attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 9 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4669' PBD 4560' Perfs 4516-40'

1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer.

2nd plug squeezed well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 500 psi and shut in pressure 200 psi

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1984  
11-20-84  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 3500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-16-84

INV. NO. 2549

Copy original back

Signed Allen W. ...  
(TECHNICIAN)