

1030222

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,164-0000

NW SE NW, SEC. 15, T 25 S, R 17 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Wheaton Well # 1-15

Operator: F. G. Holl

County Edwards

Name & Address 6427 East Kellogg

Well Total Depth 4670 163.45 feet

P. O. Box 18167

Conductor Pipe: Size _____ feet

Wichita, KS 67218

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 9 Month: July Year: 19 84

Plugging proposal received from Neal Pedicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4669' PBTD 4560' Perfs 4516 - 40'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Steve Stewart
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30 pm Day: 9 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4669' PBTD 4560' Perfs 4516-40'

1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer.

2nd plug squeezed well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 500 psi and shut in pressure 200 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-16-84

INV. NO. 2549

STATE CORPORATION COMMISSION

JUL 11 1984

7-11-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Stewart
(TECHNICIAN)