

3-24-88

1061085

API NUMBER 15- 047-21,079-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C of S/2 SE SEC. 23, T 25 S, R 17 W/EX  
330 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3395  
Operator: Grasslands Petroleum Company  
Name & Address: 111 West Douglas, Suite 507  
Wichita, KS 67202

Lease Name Carey Well # 1  
County Edwards 147.55  
Well Total Depth 4540 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 24 Month: 3 Year: 19 88

Plugging proposal received from Bill Fulls  
(company name) Kelso Casing Pulling (phone) 316-938-2457  
were: 5 1/2" at 4538' Perfs at 4456-64' Elevation 2098'GL

1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 24 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of  
sand through bailer,  
2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released  
8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2440' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION RECEIVED  
MAR 28 1988  
3-28-88  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (11) / (XXXXXXXX) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 3-29-88  
INV. NO. 20234