

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20946-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 23-25S-17W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease/Unit Name: BOGNER OWWO Well Number: 1 W  
County: EDWARDS Total Vertical Depth: 4563 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4561  
Surface Casing Size: 8.625 feet: 426

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2003 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: PUMP 100# HULLS & 30 SX COMMON CMT DOWN 4 1/2" CASING. FREEPOINT CASING. PULL TO 1150'. SPOT 10 SX GEL & 50 SX CMT. PULL CASING TO 450'. PUMP 50 SX CMT. PULL CASING TO 40'. PUMP 20 SX CMT. RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/29/2003 5:05 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4427'. PUMPED 100# HULLS & 30 SX OF COMMON CMT DOWN 4 1/2" CASING. DISPLACED WITH 65 BBL WATER. PUMPED PLUG THROUGH CASING. 1ST PLUG AT 1150' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
OCT 07 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. RECOVERED 2210' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed Richard W Yaley  
(TECHNICIAN)