

To: 1 051851 10-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,128-0000
SE SW SW, SEC. 22, T. 7 S, R. 17 X/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9723
Operator: Do Mar Oil & Gas, Inc.
Name & Address: P.O. Box 238
Liberal, KS 67905-0238

Lease Name McCarty Well # 1
County Edwards
Well Total Depth 4606 149.69 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Salvage & Casing Pulling License Number 31529
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 10 Year: 19 94

Plugging proposal received from Vernon Duntz
(company name) Mike's Salvage & Casing Pulling (phone 816-938-2943)

Work: 4 1/2" at 4560' w/100 sx cement, Perfs at 4452-56'
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, release 8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 17 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 8 5/8" wiper plug and 175 sx cement down the 8 5/8".
Maximum pressure 100 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 650' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ observe this plugging.

DATE 10-21-94
INV. NO. 41485

Signed Richard M. Lacey OCT 19 1994
(TECHNICIAN) CONSERVATION DIVISION
WICHITA, KANSAS