

2-9-88 15-047-00121-00-00

To: 1 040053
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 Drill Completion Date 4/4/60
C SW SW, SEC. 34, T 25 S, R 17 W/EX
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050
Kelso Casing Pulling, Inc. (was
Operator: Gas Marketing, Inc.)
Name &
Address Box 347
Chase, KS 67524

Lease Name Fatzer Well # 1
County Edwards 149.99
Well Total Depth 4615 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 9 Month: 2 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4615' Perfs at 4500-04, 4180-82, 4070-72' Elevation 2129'
1st plug sand back to 4020' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 9 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4020' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2428' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)
Wichita, Kansas

INVOICED observe this plugging.

DATE 2-18-88

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 19894
2-9