

11-23

1 120167

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,286-00-06
C NE NE, SEC. 35, T 25 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
660 feet from E section line

Operator License # 5420
Operator: White & Ellis Drilling Inc.
Name & Address 401 East Douglas, Suite 500
Wichita, KS 67202

Lease Name Fatzer Well # 1
County Edwards 145.44
Well Total Depth 4475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 23 Month: 11 Year: 19 88

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506
were: 4 1/2" at 4466' Open hole Elevation 2101' GL

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1988
11-29-88
CONSERVATION DIVISION
Wichita, Kansas

1st plug pump 2 sx hulls and 25 sx cement and plug
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:30 p.m. Day: 23 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 100 lbs. hulls, 25 sx cement with 100 lbs. hulls mixed in, pushed plug to 3750',
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-200 psi and shut in 0 psi (not on vacuum).

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2665' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ observe this plugging.

DATE DEC 1 1988

Signed Dean Rankin
(TECHNICIAN)

INV. NO. 22223