

To: 1 052161
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-20,996-0000
NE NE NW, SEC. 35, T. 25 S, R. 17 WEX
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8902
Operator: Sam W. Mays, Jr.
Name:
Address P.O. Box 62
Great Bend, KS 67530

Lease Name LeRoy Gatterman Well # 1
County Edwards 148.59
Well Total Depth 4572 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS

Company to plug at: Hour: 9 a.m. Day: 4 Month: 9 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-727-3410

Work: 4 1/2" at 4570' with 125 sx cement, Perfs at 4480-85'
1st plug sand back to 4412' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 125 sx cement.
Fill water well.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 4 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4412' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumped 10 sx cement down water well.

Maximum pressure 100 psi and ISIP 0.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

9999
RECEIVED
OCT 9 1997
STATE CORPORATION COMMISSION

INVOICED

I (Signature) observe this plugging.

DATE 9-11-97

INV. NO. 48973

Signed Richard M. Lacey (TECHNICIAN)