

1 040212

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-4
API NUMBER 15-047-20,331-00-00
C SW NW, SEC. 36, T 25 S, R 17 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420
Operator: White & Ellis Drilling, Inc.
Name & Address: 401 East Douglas, Suite 500
Wichita, KS 67202

3300 feet from S section line
4620 feet from E section line
Lease Name E.D. Smith Well # 1
County Edwards 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address Box 698, Great Bend, KS 67202

Company to plug at: Hour: 10:45 a.m. Day: 4 Month: 1 Year: 1989

Plugging proposal received from Jerry Allen
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4539' PBD 4487' Perfs at 4462-70' Elevation 2101' GL
1st plug pump 1 sx hulls and 25 sx common cement,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 4 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 100 lbs. hulls, 25 sx common
cement, displaced to 4200',
2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 150 psi and shut in 0 psi. Well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
CONSERVATION COMMISSION
JAN 10 1989
1-10-89
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(old / ~~xxxxxx~~) observe this plugging.
DATE 1-12-89
INV. NO. 23651

Signed Stephen J. Pfeifer
(TECHNICIAN)