

To: 1 041163  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-047-20,927-0000

E/2 SE NW, SEC. 26, T 25 S, R 17 W/4E  
3300 feet from S section line  
2970 feet from E section line

4-17

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Lease Name Turner Well # 1

Operator: Turnco Drilling, Inc.  
Name:  
Address: 3900 Broadway  
Great Bend, KS 67530

County Edwards  
Well Total Depth 4600 149.50 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 4 Year: 1996

Plugging proposal received from Darrell Miller

(company name) Mike's Testing & Salvage (phone) 316-938-2943

work: 4 1/2" at 4599' w/225 sx cement, Perfs at 4474-80'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug at 1150' with 50 sx cement,

3rd plug at 415' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 23 4 11 PM '96  
4-23-96

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 17 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand bridge through dump bailer,

Spotted plugs through 4 1/2" casing. Put gel spacer between plugs.

2nd plug at 1150' with 50 sx cement,

3rd plug at 415' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE APR 24 1996  
observe this plugging.

Signed Stephen J. Reiger (TECHNICIAN)

INV. NO. 45441