

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 047-~~20,561~~

TECHNICIAN'S PLUGGING REPORT

_____ FEET FROM N/S SECTION LINE

_____ FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 7701

LEASE NAME HUCKSTEP WELL # 1

OPERATOR: G-L-E CORPORATION
NAME & ADDRESS 518 WASHINGTON
PRATT, KS 67124

COUNTY EDWARDS

WELL TOTAL DEPTH 4641 \$150.83 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 285

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893

ADDRESS Box 847, Pratt, KS 67124

COMPANY TO PLUG AT: HOUR: 8 AM DAY: 25 MONTH: Aug YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM: Ken Gates

(COMPANY NAME) Pratt Well (PHONE) _____

WERE: 4 1/2" set @ 4641' - Perf @ 4453' - 850' recovered - bottom
Cemented to 4041 w/ 50 syf - top plugged by mixing &
pumping 2 syf hulls, 15 syf gel, 10 syf cement, 10 syf
gel, 10 syf hulls, release plug, and complete
w/ 100 syf, using 60/40 foam mix w/ 2% gel, 3% CC

PLUGGING PROPOSAL RECEIVED BY: R. Bartlett
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 10 AM DAY: 25 MONTH: Aug YEAR: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed.

Max. pump pressure @ 50#
Shut in pressure @ 0 w/ no vacuum
Cementing by Halliburton

REMARKS: _____

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1983
9-1-83
CONSERVATION DIVISION
Wichita, Kansas

SIGNED R. Bartlett
(TECHNICIAN)

INVOICED

DATE 9-14-83

W.P.V. NO. 0434-W

FORM CP-2/3
REV. 6-83