

15-047-21030-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 35 TWP. 25 RGE. 16w E/W
Location as in quarters or footage from lines:
NE NW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Oil Producers Inc., of Kansas
Lease Name Grandall #2 Well No. _____
Office Address Box 8647, Wichita, Kansas 67208
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2/23/83
Plugging completed 3/3/83
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 4463'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	472'	none
				4 1/2"	4462'	2067'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 15 sacks cement, & 4 1/2" plug to 4300'. Shot well at 3516',
3008', 2804', 2640', 2513', 2309', & 2117'. Pulled 51 joints. Plugged
well with 3 hulls, 15 gel, 70 cement, 10 gel, 1 hull, plug, & 130 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 83



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
3-14-83
MAR 14 1983

CONSERVATION DIVISION
Wichita, Kansas