

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 207B
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-19002-0000

LEASE NAME Cudney

WELL NUMBER 4

3400' Ft. from S Section Line

760' Ft. from E Section Line

SEC. 35 TWP. 25 RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 7-5-00

Plugging Completed 7-7-00

LEASE OPERATOR RAMA OPERATING CO., INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4470'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	351'	None
				4-1/2"	4468'	2500'

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each. Plugged off bottom with sand to 4250' and 4 sks. cement. Shot pipe @2500', pulled up to 1050' pumped 10 sks. gel and 50 sks. cement, pulled up to 380', pumped 50 sks. cement, pulled rest of pipe, topped off with 10 sks. cement, 60/40 pos. 6% gel. plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed i the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of July XX 2000

Jane Herzberg
Notary Public

My Commission Expires: _____

