


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 36 Twp. 25S Rge. 16 1/4 (W)
Location as "NE/CNW/SW" or footage from lines C NW/4 SW/4
Lease Owner National Cooperative Refinery Association
Lease Name Lovell Well No. 2
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 16, 19 61
Application for plugging filed September 19, 19 61
Application for plugging approved September 21, 19 61
Plugging commenced September 16, 19 61
Plugging completed September 16, 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14148 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	289'	None - Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 240 feet, set plug with 1/2 sack of hulls and 20 sacks of cement. Mudded hole to 35 feet, set plug with 1/2 sack of hulls plus 10 sacks of cement, filled on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1961
10-10-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of October 1961

My commission expires November 26, 1964

Nell McComb Notary Public.



DRILLER'S LOG

COMPANY: National Co-operative Refinery Association
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: LOVELL #2
 LOCATION: C NW/4 SW/4 Sec. 36-25-16W EDWARDS COUNTY, KANSAS
 COMMENCED: 9-6-61
 COMPLETED: 9-16-61

0	40	Surface Clay
40	230	Sand
230	289	Shale
289	1030	Shale & Red Bed
1030	1055	Anhydrite
1055	1475	Shale & Shells
1475	1975	Shale
1975	2110	Shale & Shells
2110	2560	Lime
2560	2645	Lime & Shale
2645	3000	Shale & Lime
3000	3230	Lime & Shale
3230	3400	Shale & Lime
3400	3535	Lime
3535	3650	Shale & Lime
3650	3912	Lime & Shale
3912	4172	Lime
4172	4240	Lime & Shale
4240	4448	Lime
	<u>4448</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 22 1961
 CONSERVATION DIVISION
 Wichita, Kansas

Ran 9 joints new 8 5/8" surface casing @ 289' with 225 sacks Quickset.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lovell #2, located C NW/4 SW/4 of Section 36, Township 25, Range 16 West, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

Byron Johnson
 Byron Johnson

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21st day of September, 1961

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1963