


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 36 Twp. 25 Rge. 16 (E) (W) x
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Southland Royalty Co.
Lease Name F. B. Lamb Well No. #5
Office Address 1405 Wilco Bldg. Midland, Texas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 12-2-66 19
Application for plugging approved 19
Plugging commenced 12-31-66 19
Plugging completed 1-5-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4420' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4275', mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 350', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer.
Bailed hole dry. Mixed and ran 20 sacks cement thru dump bailer. Mudded hole to 40', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1967
1-9-67

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spessard Sec
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of January, 1967

My commission expires 24 October 1968

Edmund D. Miller
Notary Public.

LAUCK DRILLING COMPANY
Incorporated

Southland Royalty Company

Lamb #5

NE NE NE Sec. 36-25S-16W
Edwards County, Kansas

Commenced: October 3, 1961
Completed: October 17, 1961

Casing Record: 385' 8-5/8" Cemented with 280 sacks cement,
6 sacks Calcium Chloride.
4420' 5-1/2" Cemented with 150 sacks cement,
40 sacks Latex.

Elevation: GR 2045; DF 2048; KB 2050.

Drillers Log

Sand	225	Lime	3700
Blue Shale	300	Shale	3705
Red Bed	338	Lime	3770
Sand	358	Shale (Douglas)	3858
Red Bed	1000	Lime	4295
Anhydrite	1020	Core	4296
Red Bed & Shale	1350	Lime & Shale	4316
Shale & Shells	1925	Core	4338
Anhydrite & Shale	2050	Shale, Lime & Chert	4350
Lime & Shale	2120	Chert	4352
Lime	2220	Core	4367
Lime & Shale	2340	Shale, Sand & Chert	4380
Lime	2540	Core	4409
Shale & Lime	3045	Chert	4410
Lime & Shale	3480	Chert & Shale	4420 RTD

I hereby certify that this is a true and correct log of the above mentioned well, to the best of my knowledge and belief.

John H. Knightley
John H. Knightley, Secretary

Subscribed and sworn to before me this 25th day of October, 1961.

Stella J. Rodwin
Notary Public

My commission expires

March 12, 1962

RECEIVED
OCT 21 1961

SOUTHLAND ROYALTY CO.
SARASOTA, FLORIDA

RECEIVED
JAN 23 1967
COMMISSION DIVISION
KANSAS