

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Edwards County, Sec. 36 Twp. 25 Rge. 16 (E) (W) x
Location as "NE/CNW*SW*" or footage from lines. SW SW NE
Lease Owner Southland Royalty Co.
Lease Name Lamb Well No. #2
Office Address 1405 Wilco Bldg. Midland, Texas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 12-2-66 19
Application for plugging approved 19
Plugging commenced 1-5-67 19
Plugging completed 1-11-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4465' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN DATE CONFIRMED BY	PULLED-OUT- DATE CONFIRMED BY
					JAN 16 1967	
					1-16-67	
					CONFIRMATION DIVISION	
					WILLIAM J. MARSHALL	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 4300', Mixed and ran 5 sacks cement thru dump bailer.

Mudded hole to 350', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer. Mixed and ran 20 sacks cement thru dump bailer. Mudded hole to 40', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. *12*

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 13 day of January, 1967

My commission expires 24 October 1968

Notary Public.

Southland Royalty Company

Lamb #2

SW SW NE 36-25S-16W

Edwards County Kansas

Drilling Contractors: Lauck Drilling Company, Inc.

Commenced: October 24, 1958

Completed: November 10, 1958

Casing Record: 388' 8 5/8" cem. with 300 sx
Calcium Chloride 6 sax
4465' 5 1/2" cem. w/ 150 sx
Lafex 45 sx

Elevation:

GR 2049; DF 2052; KB 2054

Drillers Log

Surface clay	30
sand	220
shale	320
sand	350
shale	388
red bed	1017
Anhydrite	1045
shale & shells	1615
salt & shale	1700
shale & shells	1940
lime & shale	2175
lime	2380
lime & shale	2500
lime	2655
broken lime	2710
shale & lime	3220
broken lime & shale	3330
broken lime	3465
chalky lime & shale	3570
lime & shale	3795
shale & lime	3860
lime	4180
lime & shale	4230
shale & lime	4340
shale & chert	4365
chart (Miss)	4385
shale & sand	4415
lime	4419
shale & lime	4465 R.T.D.

I hereby certify that this is a true and correct
log of the above mentioned well, to the best
of my knowledge and belief.

John H. Knightley
Subscribed and sworn to before me this

16 day of November 1958

Elizabeth Gay
Notary Public

My commission expires Sept. 14, 1959

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1967

REGISTRATION DIVISION
WICHITA, KANSAS