

15-047-20808-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
207 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 10-10-58

LEASE NAME Cudney

WELL NUMBER 3CL

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 36 TWP. 25 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 6-6-90

Plugging Completed 1:30 PM

LEASE OPERATOR NCRA

ADDRESS 6000 W. 10th, Great Bend, Kansas 67530

PHONE#(316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-6-90 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filled? yes If not, Is well log attached?         

Producing Formation          Depth to Top 4420 Bottom 4410 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	451	
				5 1/2	4459	2200:70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Bottom: 5 sks cement & sand. Top: 4h, 10ge, 50c, 10g, 1h, 125c, 60/40 6% gel. & 2% cc.  
300/200

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: NCRA

STATE OF KANSAS COUNTY OF BARTON, ss.

Gary G. Burke

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 768, Great Bend, Kansas 67530

NOTARY PUBLIC - STATE OF KANSAS  
LOVELLA L. MULLEN  
My Appt. Exp. 1-13-94

My Commission Expires: 1-13-94

Notary Public

DRILLERS LOG

File

Company Thunderbird Drilling, Inc.

Contractor Thunderbird Drilling

Farm Lovell

Elevation 2068' K.B.

Well No. 3

Casing 8 5/8" @ 451' w/400 sx

Location SW SW, Sec. 36-25S-16W

County Edwards County, Ks.

Production 5 1/2" @ 4459' w/150 sx

<u>From</u>	<u>To</u>	<u>Description</u>
0	451	Surface hole
451	1014	Redbed, Shale & Shells
1014	1057	Red bed
1057	1070	Anhydrite
1070	1430	Shale
1430	1677	Sand & Shale
1677	2105	Shale & Shells w/lime strk
2105	2265	Lime, Sand & Shale
2265	2280	Lime & Shale
2280	2385	Lime, Strks. of Shale
2385	2535	Lime & Shale
2535	2795	Shale & Lime
2795	3035	Shale & Lime Strks.
3035	3250	Shale & Lime
3250	4105	Lime & Shale
4105	4460	Lime
4460	R.T.D.	

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF SEDGWICK)

I, Burke Krueger, of Thunderbird Drilling, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Lovell #3

Burke Krueger

Subscribed and sworn to before me this 7th day of May, 1981



Gloria DeJesus  
Gloria DeJesus Notary Public

My commission expires: 3-25-84