

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 11 TWP. 25S RGE. 17W E/W
Location as in quarters or footage from lines:
SW SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner F. G. Holl
Lease Name Tubbs-Burr "B" Well No. 1-11
Office Address P. O. Box 18167, Wichita, Kansas 67218
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 7, 1983
Application for plugging filed March 7, 1983
Plugging commenced 7:00 AM March 7, 1983
Plugging completed 9:30 AM, March 7, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey and Steve
Producing formation _____ Depth to top _____ bottom T.D. 4595' Durrant

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged hole through open ended drill pipe.
50 saks at 1170' ; 40 sacks at 570' ; 40 sacks
at 300' ; Bridge 1/2 sack hulls, plug and 10 sacks
at 40' ; 10 sacks in rathole with joint of drill pipe.
Used 50/50 Pozmix, 4% gel and 3% cc.

RECEIVED
STATE CORPORATION COMMISSION
3-9-83
MAR 9 1983
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Richard L. Mead (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) Richard L. Mead
Richard L. Mead, President
P. O. Box 129, Sterling, Kansas
(Address) _____ 67579

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1983.



RECEIVED
STATE CORPORATION COMMISSION
Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

MAR 9 1983

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - TUBBS-BURR "B" #1-11
Located: SW SW SW, Section 11-25S-17W, Edwards County, Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 28, 1983
COMPLETED: March 7, 1983

TOTAL DEPTH: 4595'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 7 joints new 8 5/8", 24# casing.
90 - 298 Shale	282.51' pipe set at 295' K.B. Cemented
298 - 700 Shale, Sand, Red Beds	with 240 sacks 60/40 Pozmix with 3% cc.
700 - 1154 Shale	Plug Down at 7:30 PM, 2-28-83, by Howco.
1154 - 1170 Anhydrite	
1170 - 1770 Shale, Lime Stringers	
1770 - 4505 Lime and Shale	
4505 - 4545 Lime and Chert	
4545 - 4595 Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1983

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 3/4° at 2252'
1 7/8° at 4505'