

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
RECEIVED  
STATE CORPORATION COMMISSION

1989

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-075-20,320-0000 (of this well). 6/89  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Wallace Oil & Gas, Inc. OPERATOR'S LICENSE NO. 5855

ADDRESS 50 Penn Place, Suite 750, Oklahoma City, OK 73118 PHONE # (405) 840-2636

LEASE (FARM) McDonald WELL NO. 2 WELL LOCATION C/NW/1/4 COUNTY Hamilton

SEC. 12 TWP. 25S RGE. 39W (E) or (W) TOTAL DEPTH 2550 PLUG BACK TD 2497

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 636 CEMENTED WITH 425 SACKS

CASING SIZE 4 1/2" SET AT 2498 CEMENTED WITH 250 SACKS

PERFORATED AT 2473-98' 2462-66' 2440-48' 2400-10' 2414-21'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 40 sx cement on perfs. Cut csg @1500'. Fill hole with mud to 650'.

Cement with 50 sx from 650' to 450'. Fill with mud to 40', run 10 sx cement from 40' to surface. Cut surface

pipe 3' below surface and weld plate and date.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? \_\_\_\_\_  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

A. H. (spud) Wells PHONE # (316) 356-3410

ADDRESS Box 1114, Ulysses, KS 67880

PLUGGING CONTRACTOR Sargents Csg. Pulling LICENSE NO. 6547 6/89

ADDRESS Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]  
(Operator or Agent)

DATE: 3/10/89

①



Kansas Corporation Commission

MKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH McCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE  
JUN 14 1989  
EXPIRES

March 14, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Wallace Oil & Gas, Inc.  
50 Penn Place, Ste. 850  
Oklahoma City, OK 73118

McDonald #2  
C NW/4  
Sec. 12-25S-39W  
Hamilton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #1 304 W. McArtor  
Dodge City, KS 67530  
(316) 225-6760