

15-185-01122-0000

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Drilling Company
CONTRACTOR:	Musgrove Drilling Company
FARM:	SLADE #1
LOCATION:	SW NW SW Sec. 35-25S-12W Stafford County, Kansas
COMMENCED:	November 13, 1961.
COMPLETED:	December 4, 1961

0	301	Sand and shale
301	1710	Red bed & shale
1710	3600	Lime and shale
3600	3620	Sand, shale, lime
3620	3659	Lime
3659	4072	Lime
4072	4090	Lime & chert
4090	4190	Chert & lime
4190	4211	Shale & lime
4211	4221	Arbuckle - lime
4221	4294	Lime and dolomite
4294		Rotary T. D.

Set 8-5/8" surface at 301 feet with 300 sacks cement

Set 5-1/2" pipe at 4234' with 175 sacks 16% salt saturated cement

ELECTRIC LOG TOPS:		
Heebner	3392'	(-1529)
Toronto	3404'	(-1541)
Douglas	3425'	(-1562)
Brown Lima	3567'	(-1704)
Lansing	3592'	(-1729)
Base Kansas City	3900'	(-2037)
Marmaton	3909'	(-2046)
Mississippi	3989'	(-2126)
Viola	4048'	(-2185)
Simpson	4144'	(-2281)
Arbuckle	4212'	(-2349)

ELEVATION: Derrick Floor 1860'
Kelly Bushing 1863'

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 22 1992
7-22-92
CONSERVATION DIVISION
WICHITA, KS

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the SLADE #1, SW NW SW Section 35-25S-12W, Stafford County, Kansas, as reflected by the files of Musgrove Drilling Company.

Emil E. Bowers
Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of December, 1961.

Leah Faye Hafke
Leah Faye Hafke, Notary Public

My commission expires June 16, 1963.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1992

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1992

CONSERVATION DIVISION
WICHITA, KANSAS