

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 5 Twp. 25S Rge. ~~11~~ 12 (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner ~~McCune~~ Shawver-Armour, Inc.

Lease Name McCune Well No. 1

Office Address 817 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 9, 1963

Application for plugging filed August 9, 1963

Application for plugging approved August 9, 1963

Plugging commenced August 9, 1963

Plugging completed August 13, 1963

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4168 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 280 feet. Followed by wooden plug and 1/4 sack hulls. Placed 20 sacks cement onto hulls. Mudded up with heavy mud to 40 feet. Followed by wooden plug, 1/4 sack hulls and 15 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1963

8-23-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF ~~SEAN~~ BUTLER, ss.

JOHN C. GRAVES (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*

Box 332, El Dorado, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1963

Betty Brandt
Betty Brandt Notary Public.

My commission expires April 30, 1967



15-185-01433-0000

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Shawver-Armour, Inc.
817 Central Building
Wichita, Kansas

DRILLING COMMENCED: July 30, 1963

CONTRACTOR: Graves Drilling Co., Inc.
Box 332
El Dorado, Kansas

DRILLING COMPLETED: August 9, 1963

CASING RECORD: 9 Jts. - 283' - 8-5/8"
surface casing set with
190 sacks cement.

LOCATION: McCune No. 1
C NE SE
Section 5-25S-12W
Stafford County, Kansas

0 - 286	Sand & shale
286 - 714	Shale & red bed
714 - 729	Anhydrite
729 - 1400	Shale, red bed & sand
1400 - 1784	Shale
1784 - 2224	Lime
2224 - 2600	Lime & shale
2600 - 2960	Shale & lime
2960 - 2992	Shale & lime streaks
2992 - 3145	Shale & lime
3145 - 3335	Lime
3335 - 3470	Lime & shale
3470 - 3556	Shale & lime
3556 - 3573	Brown lime & shale
3573 - 4020	Lime
4020 - 4045	Lime & chert
4045 - 4100	Lime
4100 - 4168	Shale & sand
4168	Rotary Total Depth

STATE CORPORATION COMMISSION
 AUG 23 1963
 8-23-63
 CONSERVATION DIVISION
 WICHITA, KANSAS

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 12th day of August, 1963.

My commission expires:
April 30, 1967

Betty Brandt
Betty Brandt Notary Public