

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

STAFFORD

County. Sec. 4 Twp. 25 Rge. 12 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE

Lease Owner GLICKMAN OIL COMPANY

Lease Name MC CUNE Well No. 1

Office Address.....BOX 3108-----WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed..... July 28 19 54

Application for plugging filed..... July 28 19 54

Application for plugging approved..... July 28 19 54

Plugging commenced July 28 19 54

Plugging completed..... July 28 19 54

Reason for abandonment of well or producing formation..... DRY HOLE.....

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....Warren H. Horner.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4170 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug was set at 240 feet with 1/3 sack of hulls and 20 sacks of cement. Hole was then filled to 40 feet with heavy mud and plug was set at 35 feet with 1/3 sack of hulls and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 - 1954 8-5-54

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: **SCHAFER DRILLING COMPANY**

Address: **BOX 350---PRATT, KANSAS**

STATE OF KANSAS, COUNTY OF PRATT, ss.
J. E. Selby (employee of owner) or (owner or operator) of the above-described well
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God. *ll l l*

(Signature)

BOX 350---PRATT, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of AUGUST, 19 54

My commission expires June 30, 1955.

Notary Public.

23-8390-s 6-51--20M

PLUGGING
FILE SEC. 4 T 25 R 126
BOOK PAGE 52 LINE 44

15-185-00961-00000

DRILLER'S LOG
McCUNE #1.

GLICKMAN OIL COMPANY
Commenced July 15, 1954
Completed July 28, 1954

0-135	Surface soil, sand & clay
135-244	Red Bed
244-644	Red Bed, shale & shells
644-1350	Shale & shells
1350-1940	Shale & lime
1940-1990	Shale & salt
1990-2150	Shale & lime
2150-2330	Shale & lime shell
2330-3195	Shale & lime
3195-3248	Lime
3248-3520	Shale & lime
3520-3875	Lime
3875-3945	Conglomerate
3945-3965	Lime
3965-4000	Viola
4000-4063	Lime & chert
4063-4100	Lime
4100-4113	Sand
4113-4133	Sand & shale
4133-4170	Shale & lime
4170	TOTAL DEPTH

I certify that the above is true and correct as being taken directly from the daily drilling reports of the McCune #1.


J. E. Selby
SCHAFFER DRILLING COMPANY

STATE OF KANSAS: COUNTY OF PRATT: SS:

Subscribed and sworn to before me this 4th day of August, 1954.


Maude B. McBride
Notary Public

My commission expires June 30, 1955.

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 - 1954 8-5-54
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
7211 SEC 4 T 25 N 12W
BOOK PAGE 52 LINE 44