

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,924-0000

LEASE NAME Hearn

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-3

(50' N of SE SE NW)
3020 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Texas Energies, Inc.

SEC. 3 TWP. 25S RGE. 12 ~~XXX~~ or (W)

ADDRESS P.O. Box 947 Pratt, KS 67124

COUNTY Stafford

PHONE# (316) 672-7514 OPERATORS LICENSE NO. 5087

Date Well Completed 04-26-84

Character of Well Gas & Oil

Plugging Commenced 09-05-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-06-89

The plugging proposal was approved on 08-14-89 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Viola Depth to Top 3950 Bottom 3953 T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
				8 5/8	300	None
				4 1/2	4188	2210

10-12-89 RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
UC 1 12 1989
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set cast iron bridge plug at 3900', dumped 2 sxs cement on top with bailer. Shot off casing at 2218' and pulled. Pumped down 8 5/8" casing to spot 400# hulls and 10 sxs gel below 760', 50 sxs 60-40 pozmix cement with 6% gel 538-760', 3 sxs gel and 50# hulls 437-538'. Dropped 8 5/8" wiper plug and 100 sxs 60-40 pozmix cement with 6% gel surface to 437'. CONTINUED ON BACK
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Mark P. Stevenson (Employee of Operator) or (XXXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124



SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 89
Julia Berry
Notary Public
My Commission Expires: Feb. 6, 1993

