

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat'**

Name of Conservation Agent who supervised plugging of this well..... C. T. Alexander

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 475 Feet

Show depth and thickness of all water, oil and gas formations. 40 ft. from

OIL, GAS OR WATER RECORDS

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Rotary hole
Filled with mud to 300'
Cement bridge 300' to 285' - 16 sack
Mud 285' to 26'
Cement to 6'
Filled with mud to surface

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to:

Address.....

STATE OF Kansas, COUNTY OF Deagwick, ss.
 _____ (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
809 Petroleum Building, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 26th day of October, 1945

December 6, 1945

My commission expires.

Notary Public.

15-185-11541-0000

COMPANY: Falcon-Seaboard Drilling Co.
 CONTRACTOR: Tri-State Drilling Co., Inc.
 FARM: Jenkins, Well No. 1

LOCATION: • W/2 SW/4 NW/4
 Section 2-25-12W
 Stafford County, Kansas

COMMENCED: October 2, 1943
 COMPLETED: October 23, 1943

CASING RECORD:

8 5/8" - 660' - 275 Sacks

ELEVATION: 1862'
 PRODUCTION: D & A

FORMATION	DEPTH
Sand	133
Sand and clay	2258
Sand, clay, red bed	345
Shale, red bed & shells	600
Shale & shells	6840
Sand	652
Anhydrite	680
Shale & shells	700
Shale - red rock	865
Shale, shells, red rocks	1050
Shale & shells	1260
Salt & shale	1380
Lime & shale	1560
Anhydrite - shale	1720
Shale & shells	1825
Sand	1840
Shale & shells	1920
Lime, sandy	1985
Sand	1995
Sandy lime	2060
Lime and shale	2100
Shale - lime	2125
Lime and shale	2560
Shale & lime	2730
Lime and shale	3040
Lime	3245
Lime & shale streaks	3260
Lime & shale	3355
Shale	3370
Lime & shale	3520
Shale - lime streaks	3540
K.C. Lime	3560
Lime	3605
Lime, cherty	3635
Cherty lime	3663
Lime, cherty	3675
Lime and shale	3700
Lime	3838
Shale - lime	3845
Lime - shale, (cherty streaks)	3870
Lime & chert	3910
Conglomerate	3978
Chert	3987
Lime, cherty	4005
Chert	4040
Lime "Cherty"	4075
Shale & sand	4100
Shale	4133
Arbuckle lime	4175
TOTAL DEPTH	4175

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

Subscribed and sworn to before me this 26th day of October, 1943

Chytell Smalley
 Notary Public

My Commission expires December 6, 1945

10-27-43