

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Stafford County. Sec. 10 Twp. 25S Rge. (E) 12 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines..... SW SW SW

Lease Owner.....Phillips Petroleum Company.....

Lease Name Crawford Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed..... August 9, 1943.

Application for plugging filed.....August 23, 1943.

Application for plugging approved.....August 23, 1943.

Plugging Commenced..... August 23, 1943.

Plugging Completed..... August 23, 1943.

Reason for abandonment of well or producing formation... Drill pipe stuck, well abandoned and new hole drilled.

If a producing well is abandoned, date of last production..... 193.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....C. T. Alexander.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... **3628**..... Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with mud from top to bottom except fifteen sacks of cement and plug at 460 ft., ten sacks of cement and plug at 190 ft., and five sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beardmore Drilling Company
Address 606 Petroleum Building, Wichita, 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK ss.

F. W. Feldner, employee of operator, ~~agent~~ (employee of owner) of (owner or operator) of the above-described well

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. *Stacy*

(Signature)

9-22-43

2606 Petroleum Building, Wichita, 2, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of September 1943.

My commission expires December 6, 1943.

18-357

7-89-9M

Notary Public.

15-185-11668-0000

CRAW NO. 1 WELL

SW SW Sec. 10-25S-12W,
Stafford County, Kansas.

Drilled for: Phillips Petroleum Company
Drilled by: Beardmore Drilling Company

Casing Record:

8-5/8" 500'

Drilling Commenced: July 29, 1943.
Drilling Completed: August 9, 1943.

<u>FORMATION</u>	<u>DEPTH</u>
surface	30
sand	110
red bed	500
red rock	750
shale & shells	1425
salt & shale	1550
shale & shells	1700
shale & lime	1830
shale & lime shells	1965
shale & lime	2050
sandy lime	2075
shale & lime	2715
lime	2745
broken lime	2845
shale & lime	3030
lime	3070
shale & lime	3555
lime	3628

Note: Drill pipe stuck - unable to recover -
rig skidded - new hole drilled.

STATE OF KANSAS

SS.

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Alt. Redner

Subscribed and sworn to before me this 21st day of September, 1943.

Jane E. Macauley
Notary Public

My Commission Expires:
December 6, 1943.

