

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 18 Twp. 25 Rge. (E) 12(W)

Location as "NE/CNW/SW" or footage from lines

Lease Owner Myrtle Carohan

Lease Name Russell Well No. 1

Office Address Broadview Hotel

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-16-50 19

Application for plugging filed 11-16-50 19

Application for plugging approved 11-16-50 19


Plugging commenced 11-16-50 19

Plugging completed 11-16-50 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 4200 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
277' of 3	5/8 Surface Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 250', cemented w/20 sacks cement through drill pipe. Filled with heavy mud to 30', set second plug at 30', cemented w/10 sacks cement through drill pipe.

(If additional description is necessary, use BACK of this sheet) Broadview Hotel,

Correspondence regarding this well should be addressed to Wichita, Kansas

Address

STATE OF KANSAS, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1950

My commission expires

Oct 27, 1954

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

23-8273-s 4-50-10M

PLUGGING
FILE SEC 11 T 25 R 12W
BOOK PAGE 42 LINE 28

JAN 10 1951 1-10-51
CONSERVATION DIV
Wichita, Kans

Gabbert-Jones Drilling Co.
 Drillers Well Log

Russell #1, Stafford County, Kansas
 Commenced 10-28-50
 Completed 11-16-50

15-185-11500-0000

From	Depth	To	Formation	Remarks
0		100	Sand & Clay	
100		195	Sandy red bed	
195		276	Grey shale & Shells	
276		277	Grey shale & Shells	Run 13 jts. of 8 5/8" cemented w/150 sacks, w/ 28 sacks at top
277		735	Red bed shale & Shells	
735		755	Anahydrate	
755		790	Anahydrate	
790		990	Shale & Shells	
990		1410	Shale & Shells	
1410		1675	Salt Shale & Shells	
1675		1710	Lime	
1710		1810	Lime	
1810		1935	Lime	
1935		2235	Lime	
2235		2370	Lime	
2370		2490	Lime & Shale	
2490		2635	Lime & Shale	
2635		2705	Lime & Shale	
2705		2845	Lime & Shale Broken	
2845		2955	Lime & Shale	
2955		3005	Shale & Lime	
3005		3025	Lime	
3025		3110	Broken Lime	
3110		3210	Lime	
3210		3310	Lime	
3310		3463	Lime	
3463		3512	Lime	
3512		3580	Shale	
3580		3640	Shale & Lime	
3640		3720	Lime	
3720		3748	Lime Cherty	
3748		3848	Lime	
3848		3934	Lime	
3934		4026	Lime	
4026		4061	Lime & Chirt	
4061		4098	Lime	
4098		4125	Lime, Chirt & Shale	
4125		4177	Lime	
4177		4200	Lime	
4200		TD	Dry Hole	

12-12-50
RECEIVED
 STATE CORPORATION COMMISSION
 DEC 12 1950
 CONSERVATION DIVISION
 Wichita, Kansas

Executed, This 27th day of November 1950

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss ACKNOWLEDGMENT FOR INDIVIDUAL

Before me, the undersigned, a Notary Public, within and for said county and State, on this 27th day of November 1950, personally appeared C. L. Gabbert to me personally know to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.
 My commission expires Oct 27, 1954 Sumner Hall Notary Public

PLUGGING
 FILE SEC-1875 R/20
 PAGE-43 LINE 28