

15-185-01001-0001

THE ROXANA CORPORATION

Oil and Gas Producers

J. C. MUSGROVE
PRESIDENT
CERTIFIED GEOLOGIST 1627

1925 MAIN
P. O. BOX 1850
GREAT BEND, KANSAS 67530

JAMES C. MUSGROVE
VICE PRESIDENT

(316) 792-1383

McCune "A" #1 OWWO	<u>ELEVATIONS</u>
NE NE NE	
Sec. 18-25S-12W	1879' G.L.
Stafford County, Kansas	1902' K.B.

DAILY DRILLING REPORT

- 2- 9-84 Move in Lobo Drilling and rigged up
- 2-10-84 Drilled plug @ 9:00 a.m.
3:00 p.m. cleaning out old hole @ 2400'
- 2-11-84 Ran 105 jts new 4 1/2", 8rd, 10 1/2#, API, J-55, (Range 3) casing.
Tally 4220.35, set at 4219', One (1) foot off bottom.
Halliburton cemented with 200 sks 60/40 poz, 18% salt,
2% gel, .75 CFR2
15 bbls salt flush, 10 bbls mud flush
Plug down at 6:40 p.m.

RECEIVED
STATE CORPORATION COMMISSION
SEP 6
CONSERVATION DIVISION
Wichita, Kansas

9-6-85